

## **Manhole/Petrol Interceptor/Grease Trap/Septic Tank/Cesspool Works**

In giving this approval of plans, I hereby impose the following condition under item 7 in section 17(1) of the Buildings Ordinance:

- (a) Adequate precautionary measures and suitable working procedures should be adopted in carrying out the above works to safeguard the stability of any building, structure, land, street or services.
- (b) In this connection, two sets of plans for excavation and lateral support (ELS) works are required to be submitted.

2. Where excavation depth involved is equal to or greater than 2.5 m, you are reminded that site supervision of the ELS works by a team of supervisors shall be provided each by the Authorized Person, Registered Structural Engineer and Registered General Building Contractor in accordance with the Technical Memorandum for Supervision Plans 2009 and the Code of Practice for Site Supervision 2009 to ensure that the works are carried out in accordance with the approved plans and in such a manner as not to render inadequate the margin of safety of, or impair the stability of, or cause danger to any building, structure, land, street or services.

3. In connection with paragraph 2 above, details of site supervision of the ELS works shall be included in the supervision plan and submitted prior to or at the time of application for consent to the commencement of the ELS works.

4. Consent to the commencement and carrying out of the above works will not be given until the excavation and lateral support plans specified in paragraph 1 above have been submitted and found satisfactory/approved.