

Ref. BD _____

***[Standard Insertion List II :
List of Standard Insertion that may be included in the
approval of foundation plans]***

Please choose appropriate items

6. This approval is subject to the conditions and requirements given in #Appendix/Appendices _____ attached.
7. To ensure full compliance with the Buildings Ordinance, it is prudent for the Authorized Person who acts as the coordinator of the building works to inform the Registered General Building Contractor/Registered Specialist Contractor of all the imposed conditions attached to this approval.
8. This approval is based on the assumed loads used in the design of these foundations. The superstructural plans, when submitted, may not be approved if the loads from the detailed calculations of the superstructure differ from the loads assumed in the foundations now approved.
9. You are reminded that the approval of this submission does not infer that any general building plans corresponding to this application will be approved by the Building Authority and it is your duty to ensure that the approved structural submissions are compatible with the approved general building plans.
10. Under item 6 of Section 17(1) of the Buildings Ordinance, you are required to submit initial readings of all the monitoring stations prior to the commencement of the foundation works and subsequent monitoring readings at bi-weekly intervals during the course of works. A copy of the monitoring record shall be kept on site for inspection by staff of Buildings Department. Monitoring checkpoints should be duly monitored and assessed at various critical stages of construction works and the Registered General Building Contractor/Registered Specialist Contractor should regularly update the works programme of site activities.
11. Under Building (Administration) Regulation 10, you are required to submit a pre-construction condition survey report on the ground, the adjacent structures and services located within and in the vicinity of the site. The area to be surveyed shall cover at least _____ m from the perimeter of the site. Under section 16(3)(b) of the Buildings Ordinance, the consent for the commencement of foundation works will not be given until the report has been submitted and found satisfactory.
12. The Public Relation Plan (PR Plan) submitted on _____ is hereby acknowledged. Please ensure that prompt and effective communication with the occupants of adjacent buildings should be taken in accordance with the PR Plan submitted during the course of the works.
13. You are reminded that the record plans and/or test reports required under

this approval should be submitted within the time frame as specified in the attached appendix/appendices. Delay in the submission of the required documents may affect the timely processing of Form BA14 and/or occupation permit applications.

Below standard paragraph is applicable if the Form BA14 to certify completion of GIFW has been submitted but is yet to be acknowledged due to comments on site supervision plan

It is noted that the Form BA 14 submitted by you on _____ to certify the completion of the ground investigation works is not yet accepted by this Department. Your attention is drawn to my letter dated _____ under the reference _____ regarding comments on the supervision plans for the ground investigation works. Under Section 16(3)(b) of the Buildings Ordinance, consent to the commencement and carrying out of the works now approved will not be given until the said Form BA14 has been acknowledged by the Department.

Below standard paragraphs are for stipulating temporary steel platforms proposal

You are reminded that if temporary steel platforms are needed to be erected on slopes and/or top of retaining walls to carry plants and machineries in order to facilitate the foundation construction works now approved, plans showing relevant details of the temporary steel platforms including their foundation supports should be submitted for approval/consideration.

Consent to the commencement and carrying out of the foundation works will not be given until the details specified in paragraph _____ above have been approved or found satisfactory.

You are advised to check if there are any dangerous slopes (government or private) in the vicinity of the site and the effects of the proposed temporary steel platform works on the stability of such slopes. Information on the classifications of slopes are given in the Stage 2 Reports prepared by the consultants of Civil Engineering Development Department (CEDD) which is available for viewing by public in the CEDD library. If the slopes are classified as dangerous, you should submit a geotechnical assessment report to ensure Building Authority that the stability of such slopes would not be affected by the proposed temporary steel platform works. Otherwise, suitable precautionary measures and monitoring systems should be provided during the course of the works.

Below standard paragraphs are for stipulating static plate loading test

Under item 6 of Section 17(1) of the Buildings Ordinance, static plate loading tests should be carried out to verify the adequacy of the allowable bearing capacity of the founding stratum. In this connection, the testing procedures and acceptance criteria are required to be submitted. Consent to the commencement and carrying out of the _____ works will not be given until the details of the static plate load test as specified have been submitted and found

satisfactory.

In connection with paragraph _____ above regarding to the static plate loading tests, the Buildings Department should be notified of the time and date of the test so that they may be witnessed by a representative from the Department.

Delete wherever inapplicable.