

### Non-loadbearing Partition Walls

The construction and demolition of non-loadbearing partition walls are frequent operations in the construction process, in particular alterations and additions works. Although these walls are not structural elements, it is necessary in the interest of safety for authorized persons (APs) and registered structural engineers (RSEs) to ensure that the design and construction of the works achieve the required performance standard.

2. In the light of the observation in a study of an accident involving the collapse of a non-loadbearing partition wall, this practice note is issued to give guidance to protect public safety in respect of works involving non-loadbearing partition walls.

#### Design and Construction of Non-loadbearing Partition Walls

3. In the design and construction of non-loadbearing partition walls, APs and RSEs should ensure that all factors which may affect their stiffness and stability, such as slenderness, supports and restraints, are taken into account. Their design and construction should be in accordance with relevant standards and codes of practice. In this respect, PNAP 140 should be referred to.

#### Demolition of Non-loadbearing Partition Walls

4. When non-loadbearing partition walls are to be demolished, APs and RSEs should ensure that :

- appropriate precautionary measures are provided as site situation demands;
- the works are carried out by experienced workers; and
- adequate supervision is provided throughout the demolition period.

In this connection, attention is drawn to PNAP 71.

  
(CHOI Yuleuk)  
Building Authority

Ref. : BD GP/BOP/33

First issued October 1996 (AD/D, AD/SE)

Index under : Non-loadbearing Partition Wall  
Partition Wall