

## **Reinforced Concrete Works**

In giving this approval of plans, I hereby impose the following conditions under item 6 in section 17(1) of the Buildings Ordinance:

- (a) Sampling and testing of steel reinforcing bars should be carried out in accordance with CS2:2012. Testing should be carried out by a laboratory\* accredited under the Hong Kong Laboratory Accreditation Scheme (HOKLAS) for the particular test concerned. Test results<sup>®</sup> should be submitted within 60 days of the delivery of the steel reinforcing bars to the site<sup>^</sup>. The test reports should be appended with a statement signed by the Registered Structural Engineer to confirm the following:
  - (i) All steel reinforcing bars used for the construction and the test specimens covered by the test reports are in accordance with the types and grades of steel shown in the approved plans.
  - (ii) Sampling and testing of steel reinforcing bars used have been carried out in accordance with CS2:2012.
  - (iii) The acceptance criteria appropriate to each type and grade of steel reinforcing bars used have been complied with.
  - (iv) All steel reinforcing bars tests have been carried out by a laboratory\* accredited under the HOKLAS.
  
- (b) Sampling of concrete and compression testing of concrete test cubes should be carried out in accordance with the methods specified in CS1:2010. Testing should be carried out by a laboratory\* accredited under the HOKLAS for the particular test concerned. Test results<sup>®</sup> should be submitted within 21 days after testing. The test reports should be appended with a summary which contains information on locations of concerned structural elements, concrete grades and dates of cast. The summary should also include previous summary information of concrete cube test reports in chronological order. The test reports should also be appended with a statement signed by the Registered Structural Engineer to confirm the following:
  - (i) All concrete used for the construction and concrete cubes covered by the test reports are in accordance with the concrete grades shown in the approved plans.
  - (ii) Concrete cube sizes, rates of sampling fresh concrete for testing and acceptance criteria for compressive strength set out in Building (Construction) Regulations have been complied with.
  - (iii) All concrete cube tests have been carried out by a laboratory\* accredited under the HOKLAS and in accordance with the methods specified in CS1:2010.
  
- (c) Concrete should be obtained from concrete suppliers certified under the Quality Scheme for the Production and Supply of Concrete except for those

exceptional projects permitted under clause 11.7.1 of the Code of Practice for Structural Use of Concrete 2013 where documents should be submitted by the Registered Structural Engineer at least one week prior to commencement of the works to prove that the concrete supplier is operating under an approved quality system.

2. The following conditions in respect of qualified supervision of works are imposed under item 6 in section 17(1) of the Buildings Ordinance:

- (a) Qualified site supervision of the reinforced concrete works, including sampling of concrete and steel reinforcing bars and making and curing of test cubes, by experienced and competent persons as defined in 2(b) and 2(c), should be provided to ensure that the works are carried out in accordance with the plans approved and that the required standards are complied with.
- (b) The Registered Structural Engineer should assign a quality control supervisor to supervise the works, determine the necessary frequency of inspection by the quality control supervisor which should not be less than once a week, and devise inspection check lists. The minimum qualifications and experience of the quality control supervisor is to be the same as the Technically Competent Person of grade T3 under the Registered Structural Engineer's stream, as stipulated in the Code of Practice for Site Supervision 2009.
- (c) The Registered General Building Contractor/Registered Specialist Contractor should assign a quality control co-ordinator to provide full time on site supervision of the works and devise inspection check lists. The minimum qualifications and experience of the quality control co-ordinator is to be the same as the Technically Competent Person of grade T1 under the Registered General Building Contractor's/Registered Specialist Contractor's stream, as stipulated in the Code of Practice for Site Supervision 2009.
- (d) The names and qualifications of the supervisory personnel representing the Registered Structural Engineer and the Registered General Building Contractor/Registered Specialist Contractor respectively should be recorded in an inspection log book. The date, time, items inspected and inspection results should be clearly recorded in the log book. The log book should be kept on site for inspection by representatives of the Buildings Department.

3. Where steel reinforcing bar (rebar) products such as cut and bent rebars, reinforcement cages and the like are fabricated off-site in a prefabrication yard, the following conditions in respect of qualified supervision of *off-site rebar prefabrication works* (referred hereafter as "Prefabrication Works"<sup>+</sup>) are imposed under item 6 in section 17(1) of the Buildings Ordinance:

- (a) Qualified site supervision of the Prefabrication Works<sup>+</sup>, including sampling of steel reinforcing bars, by experienced and competent persons as defined in 2(b) and 2(c), should be provided to ensure that the works are carried out in accordance with the plans approved and that the required standards are complied with.
- (b) The names and qualifications of the supervisory personnel representing the Registered Structural Engineer and the Registered General Building

Contractor/Registered Specialist Contractor respectively should be recorded in an inspection log book. The date, time, items inspected and inspection results should be clearly recorded in the log book. The log book should be kept in the prefabrication yard and a copy of it should be kept on site for inspection by representatives of the Buildings Department.

- \* A Directory of Accredited Laboratories in Hong Kong is obtainable from the Hong Kong Accreditation Service (HKAS) Executive, Innovation and Technology Commission.

A laboratory's accreditation for an individual test or calibration may be granted, modified or withdrawn at any time. Up-to-date information on accredited laboratories and their scopes of accreditation are available on the internet at the HKAS website at <http://www.itc.gov.hk/hkas/>.

- @ The test carried out by an accredited laboratory should be within its scope of accreditation. To ensure this, test results should be reported on a HOKLAS Endorsed Certificate or equivalent Certificate/Report issued from other laboratory accreditation bodies which have reached mutual recognition agreements/arrangements with the HOKLAS.
- ^ The 'site' refers to the prefabrication yard for cases covered by paragraph 3 above.
- + Prefabrication Works refer to the fabrication works of steel rebar products, such as cut and bent rebars, reinforcement cages and the like, covered by this approval of plans carried out in the prefabrication yard.