

Century Well Construction Ltd.
35-38/F, Nina Tower
8 Yeung Uk Road, Tsuen Wan
New Territories
(Attn: CHAN Man Kai)

Dear Mr. CHAN,

Letter of In-principle Acceptance
(Acceptance Reference No.: MiC 16/2025)

_____ This letter is issued to **Century Well Construction Ltd.** to confirm that the Modular Integrated Construction (MiC) system (**Model No. CCG-RC01**) as submitted to the Buildings Department (BD) is acceptable in principle for use in private building projects in Hong Kong in respect of the performance aspects listed in Appendix I, subject to the following conditions:

- _____ (i) The design and construction of any building project adopting the above MiC system shall comply with the provisions of the Buildings Ordinance (BO) and its subsidiary legislations;
- _____ (ii) The conditions as set out in Appendix II and Appendix III shall be complied with;
- _____ (iii) The modular units of the above MiC system shall be fabricated in the factories listed in Appendix IV with a valid ISO 9001 or equivalent quality assurance certification; and
- (iv) This in-principle acceptance (IPA) is valid for 5 years from the date of this letter.

2. General information of the MiC System (Model No. CCG-RC01) submitted by Century Well Construction Ltd. is available on BD's website.

/3. ...

3. Upon expiry of the IPA, application for its renewal should be prepared by an Authorized Person (AP) and Registered Structural Engineer (RSE). In case different AP and RSE are to be appointed, you are reminded to clarify any copyright issues.

4. This IPA shall not be construed as an exemption from obtaining prior approval and consent from the Building Authority under the BO before commencement of building works nor the granting of any exemption in gross floor area calculation.

5. This IPA does not give any warranties, explicit or implied, regarding their availability, efficacy, fitness for a particular purpose, title or non-infringement of copyright. The manufacturer/supplier/user must ensure that the above MiC system is safe for public use and complies with all relevant legislation and statutory requirements at all times.

Yours faithfully,

(Digitally signed by)
(CHAN Wai-tong, Victor)
Chief Officer/Technical Services
for Director of Buildings

c.c. YIU Shuk Yin (Authorized Person)
c/o Ajar Limited
Room 105, 1/F Enterprise Building
228 Queen's Road Central
Hong Kong

CHEUNG Yiu-sun, Wilson (Registered Structural Engineer)
c/o Wilson & Associates Limited
Room 1608-09
Nan Fung Commercial Centre
19 Lam Lok Street, Kowloon Bay, Kowloon

BD/MiC/240201(S)

**Applicable Performance Aspects
for In-principle Acceptance Reference No. MiC 16/2025**

The in-principle acceptance covers the following performance aspects of MiC system (Model No. CCG-RC01) of Century Well Construction Ltd. under the Buildings Ordinance (BO) and its subsidiary legislations:

- (a) Provisions of means of escape required under Part B of the Code of Practice for Fire Safety in Buildings 2011 (FS Code) and regulation 41(1) of Building (Planning) Regulations (B(P)R);
 - (b) Provisions for fire resisting construction required under Parts C and E of the FS Code and section 35 of Building (Construction) Regulation (B(C)R);
 - (c) Construction of external wall, cladding and curtain wall pursuant to sections 27, 28, 29 to 31 respectively of B(C)R;
 - (d) Height of storeys and provisions of natural lighting and ventilation required under regulations 24, 30 and 36 of B(P)R;
 - (e) Sanitary provisions and associated drainage works within the modular units pursuant to Building (Standards of Sanitary Fitments, Plumbing, Drainage Works and Latrines) Regulations;
 - (f) Structural performance for loads required under the Code of Practice on Wind Effects in Hong Kong 2019, the Code of Practice for Dead and Imposed Loads 2011 and Part 3 of B(C)R; and
 - (g) Provisions for structural performance required under the Code of Practice for Structural Use of Concrete 2013, the Code of Practice for Precast Concrete Construction 2016 and B(C)R.
2. For other performance aspects of the MiC system under the purview of the BO not listed above, compliance with the provisions of the BO and the subsidiary legislations shall be demonstrated when plans are submitted for approval under the BO.

**Acceptance Conditions (Building)
for In-principle Acceptance Reference No. MiC 16/2025**

The in-principle acceptance (IPA) of MiC system (Model No. CCG-RC01) of Century Well Construction Ltd. is subject to the following conditions:

- (a) This IPA is confined to adopting the MiC system for domestic use in a building not exceeding 50 storeys (maximum modular units of 44 storeys) as applied for;
- (b) The design and construction of the MiC system should follow the plans accepted by the Buildings Department (Accepted Plans) and tally with the testing criteria of the submitted test reports. If alternative designs, materials or construction methods different from that shown in the Accepted Plans are used, compliance with the relevant provisions under the Buildings Ordinance (BO) and the subsidiary legislations should be demonstrated when plans are submitted for approval under the BO;
- (c) Authorized Person of the development project adopting the MiC system (AP) should ensure valid test and/or assessment reports complying the requirements under Part E of the Code of Practice for Fire Safety in Buildings 2011 would be available before the actual production in the prefabricated factory;
- (d) Applicant and AP should observe the requirements under Practice Note for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers APP-13 on submission of Schedule of Building Materials and Products and certifying the compliance with the relevant provisions of the BO upon completion of works;
- (e) User manual with maintenance and building safety instructions for future fitting, decoration, alterations and additions of the modules should be provided to the owners/occupants/users of the building adopting this MiC system.

/(f) ...

- (f) The IPA is subject to the grant of exemption/modification under section 42 of the BO for the following which would be favorably considered when relevant plans are submitted for approval under the BO:

BO/Building Regulations	Description
Regulation 35A of Building (Planning) Regulations	To accept non-provision of gas aperture in the bathroom in domestic premises
Regulation 36 of Building (Planning) Regulations	To permit the omission in standard of natural lighting and ventilation in internal bathrooms
Regulation 29(1) and 29(2) of Building (Standards of Sanitary Fitments, Plumbing, Drainage Works and Latrines) Regulations	To permit the provision of cleaning access to be other than cleaning eye
Regulation 44(4) of Building (Standards of Sanitary Fitments, Plumbing, Drainage Works and Latrines) Regulations	To permit protection of cast iron pipes to be other than asphaltic coating
Regulation 50(2) of Building (Standards of Sanitary Fitments, Plumbing, Drainage Works and Latrines) Regulations	To permit jointing of cast iron pipes to be other lead caulking

**Acceptance Conditions (Structural)
for In-principle Acceptance Reference No. MiC 16/2025**

The in-principle acceptance (IPA) of MiC system (Model No. CCG-RC01) of Century Well Construction Ltd. is subject to the following conditions:

- (a) The design and construction of MiC system should follow the plans accepted by the Buildings Department (Accepted Plans) and tally with the testing criteria of the submitted test reports. If alternative designs, materials, proprietary products or construction methods different from that shown in the Accepted Plans are used, compliance with the relevant provisions under the Buildings Ordinance (BO) and the subsidiary legislations should be demonstrated when future plans are submitted for approval under the BO;
- (b) The MiC system is accepted based on the assumptions listed below. Overall stability, structural analysis, adequacy of structural member and/or structural connections, lateral deflection etc. should be checked when there are any deviations with future structural plans submitted for approval under the BO.
 - (i) Maximum building height from ground floor to main roof is 175.7m;
 - (ii) Maximum number of storeys of modular units is 44;
 - (iii) Maximum design wind pressure at main roof is 3.44 kPa (unfactored);
 - (iv) The imposed loads, superimposed loads and assumed facade loads are as shown on drawing nos. MIC-FP-004, MIC-FP-006B and MiC-FP-008. The imposed loads for vehicular traffic and parking are not considered;
 - (v) The lateral stability is provided by both MiC modules units and in-situ reinforced concrete core as shown on drawing no. MIC-GN-001;
 - (vi) The fabrication and installation tolerances of modular units are as shown on drawing no. MIC-GN-001;
 - (vii) Only one storey of modular units are allowed to be stacked above a completed floor as shown on drawing no. MIC-GN-001.

/ (c) ...

- (c) Proposals of the following items should be submitted for acceptance to demonstrate and assure the quality of construction and justify the design assumptions prior to the future approval of submission of building development adopting the MiC system under this IPA:
- (i) Full-scale mockup of MiC modules with composite walls using modified confinement arrangement as shown on drawing nos. MiC-GN-004, MiC-DD-001, MiC-DD-011, MiC-DD-013 and MiC-DD-014.
 - (ii) Full-scale mockup of structural wall connections using full height corrugated duct for lapping reinforcement as shown on drawing nos. MiC-GN-005, MiC-DD-002, MiC-DD-012, MiC-DD-015 and MiC-DD-016.
 - (iii) Testing to verify the load-carrying capacity and ductility performance of composite wall with modified confinement arrangement as shown on drawing no. MiC-GN-004.
 - (iv) Testing to verify the assumed design bond strength of the corrugated duct adopted in structural walls as shown on drawing no. MiC-GN-005.
- (d) Structural details of external walls, A/C platforms, protective barriers, in-situ floors (floors above R/F, refuge floor, 1/F and below floors), in-situ portions from 2/F to R/F, and MiC portions between grid lines B1~C5 and BA~BD from 2/F to R/F as shown on drawing nos. MiC-FP-003 to MiC-FP-004 and MiC-FP-007 to MiC-FP-008 are not included in this acceptance.

Manufacturer and Prefabrication Factory

Details of the accepted manufacturer and prefabrication factory for fabrication of the modular units under In-principle Acceptance reference no. MiC 16/2025 for MiC system (Model No. CCG-RC01) of Century Well Construction Ltd. are as follows:

Manufacturer: Century Well Construction Ltd.

<u>Prefabrication Factory</u>	<u>Address of Prefabrication Factory</u>	<u>Production</u>
廣州建築灣區智造科技有限公司	廣東省廣州市黃埔區夏港街道西基輓鋼路 19 號	Fabrication of modular units

Remarks:

- (a) *The above factory shall maintain a valid ISO 9001 or equivalent quality assurance certification at all times.*
- (b) *The following items in the Quality Assurance Scheme are for information only. Updated information should be submitted for future building projects with MiC.*
 - (i) *Frequency and extent of inspection by in-house staff and independent parties required in Appendix B of Practice Note for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers (PNAP) ADV-36; and*
 - (ii) *Frequency and extent of audit by in-house staff and independent parties required in Appendix B of PNAP ADV-36.*