



YOUR REF 來函檔號：
OUR REF 本署檔號： (7) in BD/MiC/190701
FAX 圖文傳真： 2523 9380
TEL 電話： 3842 3052
WEBSITE 網址： www.bd.gov.hk

24 January 2022

MDM Group Inc. Ltd.
Unit 209A, 2/F Photonics Centre,
No. 2 Science Park East Avenue,
Hong Kong Science Park, Shatin, N.T.
Hong Kong

Dear Sir/Madam,

**Letter of In-principle Acceptance
(Acceptance Reference No.: MiC 01/2022)**

This letter is issued to **MDM Group Inc. Ltd.** to confirm that the Modular Integrated Construction (MiC) system (Model No. **HRR-IC**) as submitted to the Buildings Department (BD) is acceptable in principle for use in private building projects in Hong Kong in respect of the performance aspects listed in Appendix I, subject to the following conditions:

- (i) The design and construction of any building project adopting the above MiC system shall comply with the provisions of the Buildings Ordinance (BO) and its subsidiary legislations;
- (ii) The conditions as set out in Appendix II and Appendix III shall be complied with;
- (iii) The modular units of the above MiC system shall be fabricated in the factories listed in Appendix IV with a valid ISO 9001 or equivalent quality assurance certification; and
- (iv) This in-principle acceptance (IPA) is subject to a validity period expiring on 24 January 2027.

General information of the MiC System (Model No. HRR-IC) submitted by MDM Group Inc. Ltd. is available on BD's website.

/This ...

This IPA shall not be construed as an exemption from obtaining prior approval and consent from the Building Authority under the BO before commencement of building works nor the granting of any exemption in gross floor area calculation.

This IPA does not give any warranties, explicit or implied, regarding their availability, efficacy, fitness for a particular purpose, title or non-infringement of copyright. The manufacturer/supplier/user must ensure that the above MiC system is safe for public use and complies with all relevant legislation and statutory requirements at all times.

Yours faithfully,



(Ms CHAN Yuen-ming, Mary)
Chief Officer/Technical Services
for Director of Buildings

c.c. CHE Kwai Leung Chris (Authorized Person)
c/o P&T Architects and Engineers Limited
33/F, 633 King's Road, North Point,
Hong Kong

LEUNG Wai Man (Registered Structural Engineer)
c/o P&T Architects and Engineers Limited
33/F, 633 King's Road, North Point,
Hong Kong

BD/MiC/190701(S)

**Applicable Performance Aspects
for In-principle Acceptance Reference No. MiC 01/2022**

The in-principle acceptance covers the following performance aspects of MiC system (Model No. HRR-IC) of MDM Group Inc. Ltd. under the Buildings Ordinance (BO) and its subsidiary legislations:

- (a) Provisions of means of escape required under Part B of the Code of Practice for Fire Safety in Buildings 2011 (FS Code) and regulation 41(1) of Building (Planning) Regulations (B(P)R);
- (b) Provisions for fire resisting construction required under Parts C and E of the FS Code and section 35 of Building (Construction) Regulation (B(C)R);
- (c) Construction of external wall pursuant to section 27 of B(C)R;
- (d) Height of storeys and provisions of natural lighting and ventilation required under regulations 24, 30 and 36 of B(P)R;
- (e) Sanitary provisions and associated drainage works within the modular units pursuant to Building (Standards of Sanitary Fitments, Plumbing, Drainage Works and Latrines) Regulations;
- (f) Structural performance for loads required under the Code of Practice on Wind Effects in Hong Kong 2004, the Code of Practice for Dead and Imposed Loads 2011 and Part 3 of B(C)R; and
- (g) Provisions for structural performance required under the Code of Practice for Structural Use of Steel 2011, the Code of Practice for Structural Use of Concrete 2013, the Code of Practice for Precast Concrete Construction 2016 and B(C)R.

For other performance aspects of the MiC system under the purview of the BO not listed above, compliance with the provisions of the BO and the subsidiary legislations shall be demonstrated when plans are submitted for approval under the BO.

**Acceptance Conditions (Building)
for In-principle Acceptance Reference No. MiC 01/2022**

The in-principle acceptance (IPA) of MiC system (Model No. HRR-IC) of MDM Group Inc. Ltd. is subject to the following conditions:

- (a) This IPA is confined to adopting the MiC system for domestic use in a building not exceeding 41 storeys (maximum modular units of 40 storeys) as applied for;
- (b) The design and construction of the MiC system should follow the plans accepted by the Buildings Department (Accepted Plans) and tally with the testing criteria of the submitted test reports. If alternative designs, materials or construction methods different from that shown in the Accepted Plans are used, compliance with the relevant provisions under the Buildings Ordinance (BO) and the subsidiary legislations should be demonstrated when plans are submitted for approval under the BO;
- (c) Authorized Person of the development project adopting the MiC system (AP) should ensure valid test and/or assessment reports complying the requirements under Part E of the Code of Practice for Fire Safety in Buildings 2011 would be available before the actual production in the prefabricated factory;
- (d) Applicant and AP should observe the requirements under Practice Note for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers APP-13 on submission of Schedule of Building Materials and Products and certifying the compliance with the relevant provisions of the BO upon completion of works;
- (e) User manual with maintenance and building safety instructions for future fitting, decoration, alterations and additions of the modules as submitted with the application for IPA should be provided to the owners/occupants/users of the building adopting this MiC system; and

/(f) ...

- (f) The IPA is subject to the grant of exemption/modification under section 42 of the BO for the following which would be favorably considered when relevant plans are submitted for approval under the BO:

BO/Building Regulations

Description

Regulation 35A of Building
(Planning) Regulations

To accept non-provision of
gas aperture in the bathroom
in domestic premises.

Regulation 36 of Building
(Planning) Regulations

To permit the omission in
standard of natural lighting
and ventilation in internal
bathrooms.

**Acceptance Conditions (Structural)
for In-principle Acceptance Reference No. MiC 01/2022**

The in-principle acceptance (IPA) of MiC system (Model No. HRR-IC) of MDM Group Inc. Ltd. is subject to the following conditions:

- (a) The design and construction of MiC system should follow the plans accepted by the Buildings Department (Accepted Plans) and tally with the testing criteria of the submitted test reports. If alternative designs, materials, proprietary products or construction methods different from that shown in the Accepted Plans are used, compliance with the relevant provisions under the Buildings Ordinance (BO) and the subsidiary legislations should be demonstrated when future plans are submitted for approval under the BO;
- (b) The MiC system is accepted based on the assumptions listed below. Overall stability, structural analysis, adequacy of structural member and/or structural connections, lateral deflection etc. should be checked when there are any deviations with future structural plans submitted for approval under the BO.
 - (i) Maximum building height from Ground Floor of 139.70 m;
 - (ii) Maximum modular units of 40 storeys;
 - (iii) Maximum design wind pressure of 3.18 kPa (unfactored);
 - (iv) Imposed loads, superimposed loads and assumed façade loads as shown on drawing no.: E-02-2. Imposed loads for vehicular traffic and parking are not considered;
 - (v) Lateral stability is provided by modular units and in-situ portions as shown on drawing no.: E-01-1;
 - (vi) Fabrication and installation tolerances of modular units as shown on drawing no.: E-01-1.
 - (vii) No modular units are stacked more than one-storey above the completed level of each zone as shown on drawing no.: E-07-1.

- (c) A full-scale mockup is required prior to the commencement of the construction works. A performance report should be submitted for acceptance prior to the commencement of module installation. The performance report shall also include a review on the production and installation method.
- (d) Trial panel(s) with structural testing should be carried out to verify the performance of the proposed design. The arrangement and acceptance criteria of the test is shown on drawing no.: E-01-2. The test result should be submitted and found satisfactory by the Building Authority prior to the consent application of the proposed works.
- (e) Structural details of in-situ part (in-situ floor at corridor, lift lobby & staircase; core-walls at lift and staircase) from 1/F to 40/F as shown on drawing no.: E02-1, whole floor at G/F, UR/F and TR/F are not included in this acceptance.

Manufacturer and Prefabrication Factory

Details of the accepted manufacturer and prefabrication factory for fabrication of the modular units under In-principle Acceptance reference no. MiC 01/2022 for MiC system (Model No. HRR-IC) of MDM Group Inc. Ltd. are as follows:

Manufacturer: MDM Group Inc. Ltd.

Prefabrication Factory

MDM Group Inc. Ltd.

Address of Prefabrication Factory

中國廣東省惠州市惠陽區淡水洋納村黃沙地段
(廣東中民築友科技有限公司生產裝配車間)

Remarks:

- (a) *The above factory shall maintain a valid ISO 9001 or equivalent quality assurance certification at all times.*
- (b) *The following items in the Quality Assurance Scheme are for information only. Updated information should be submitted for future building projects with MiC.*
 - (i) *Frequency and extent of inspection by in-house staff and independent parties required in Appendix B of Practice Notes for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers (PNAP) ADV-36;*
 - (ii) *Frequency and extent of audit by in-house staff and independent parties required in Appendix B of PNAP ADV-36; and*
 - (iii) *Details of laboratories for quality control tests.*