

30 July 2020

Wing Hong Shun Enterprises Limited
Unit 2221, Grandtech Centre
No.8 On Ping Street
Shatin, Hong Kong

Dear Sir/Madam,

**Letter of In-principle Acceptance
(Acceptance Reference No.: MiC 13/2020)**

This letter is issued to **Wing Hong Shun Enterprises Limited** to confirm that the Modular Integrated Construction (MiC) system (Model No. **MIC-RC-001**) as submitted to the Buildings Department (BD) is acceptable in principle for use in private building projects in Hong Kong in respect of the performance aspects listed in Appendix I, subject to the following conditions:

- (i) The design and construction of any building project adopting the above MiC system shall comply with the provisions of the Buildings Ordinance (BO) and its subsidiary legislations;
- (ii) The conditions as set out in Appendix II and Appendix III shall be complied with;
- (iii) The modular units of the above MiC system shall be fabricated in the factories listed in Appendix IV with a valid ISO 9001 or equivalent quality assurance certification; and
- (iv) This in-principle acceptance (IPA) is subject to a validity period expiring on 30 July 2025.

General information of the MiC System (Model No. MIC-RC-001) submitted by Wing Hong Shun Enterprises Limited is available on BD's website.

This IPA shall not be construed as an exemption from obtaining prior approval and consent from the Building Authority under the BO before commencement of building works nor the granting of any exemption in gross floor area calculation.

This IPA does not give any warranties, explicit or implied, regarding their availability, efficacy, fitness for a particular purpose, title or non-infringement of copyright. The manufacturer/supplier/user must ensure that the above MiC system is safe for public use and complies with all relevant legislation and statutory requirements at all times.

Yours faithfully,



(AU YEUNG Hoi-pang)
Chief Officer/Technical Services
for Director of Buildings

c.c. YUNG Hun-tat, Arthur
(Authorized Person and Registered Structural Engineer)
c/o Arthur Yung and Associates Company Ltd.
17/F, Hong Kong Jewellery Building
178-180 Queen's Road Central
Hong Kong

BD/MiC/191002(S)

**Applicable Performance Aspects
for In-principle Acceptance Reference No. MiC 13/2020**

The in-principle acceptance covers the following performance aspects of MiC system (Model No. MIC-RC-001) of Wing Hong Shun Enterprises Limited under the Buildings Ordinance (BO) and its subsidiary legislations:

- (a) Provisions of means of escape required under Part B of the Code of Practice for Fire Safety in Buildings 2011 (FS Code) and regulation 41(1) of Building (Planning) Regulations (B(P)R);
- (b) Provisions for fire resisting construction required under Parts C and E of the FS Code and regulation 90 of Building (Construction) Regulations (B(C)R);
- (c) Construction of external wall pursuant to regulation 38 of B(C)R;
- (d) Height of storeys and provisions of natural lighting and ventilation required under regulations 24, 30 and 36 of B(P)R;
- (e) Sanitary provisions and associated drainage works of the modular unit pursuant to Building (Standards of Sanitary Fitments, Plumbing, Drainage Works and Latrines) Regulations;
- (f) Structural performance for loads required under Code of Practice on Wind Effects in Hong Kong 2004, Code of Practice for Dead and Imposed Loads 2011 and Part III of B(C)R; and
- (g) Provisions for structural performance required under Code of Practice for Structural Use of Concrete 2013, Code of Practice for Precast Concrete Construction 2016 and B(C)R.

2. For other performance aspects of the MiC system under the purview of the BO not listed above, compliance with the provisions of the BO and the subsidiary legislations shall be demonstrated when plans are submitted for approval under the BO.

**Acceptance Conditions (Building)
for In-principle Acceptance Reference No. MiC 13/2020**

The in-principle acceptance (IPA) of MiC system (Model No. MIC-RC-001) of Wing Hong Shun Enterprises Limited is subject to the following conditions:

- (a) This IPA is confined to a standalone single storey MiC module for occupation by a single family;
- (b) The design and construction of the MiC system should follow the plans accepted by the Buildings Department (accepted plans) and tally with the testing criteria of the submitted test reports. If alternative designs, materials or construction methods different from that shown in the accepted plans are used, compliance with the relevant provisions under the Buildings Ordinance (BO) and the subsidiary legislations should be demonstrated when plans are submitted for approval under the BO;
- (c) Authorized Person of the development project adopting the MiC system (AP) should ensure valid test and/or assessment reports complying the requirements under Part E of the Code of Practice for Fire Safety in Buildings 2011 would be available before the actual production in the prefabricated factory;
- (d) Applicant and AP should observe the requirements under Practice Note for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers APP-13 on submission of Schedule of Building Materials and Products and certifying the compliance with the relevant provisions of the BO upon completion of works; and
- (e) User manual with maintenance and building safety instructions for future fitting, decoration, alterations and additions of the modules as submitted with the application for IPA should be provided to the owners/occupants/users of the building adopting this MiC system.

**Acceptance Conditions (Structural)
for In-principle Acceptance Reference No. MiC 13/2020**

The in-principle acceptance (IPA) of MiC system (Model No. MIC-RC-001) of Wing Hong Shun Enterprises Limited is subject to the following conditions:

- (a) The design and construction of MiC system should follow the plans accepted by the Buildings Department (accepted plans) and tally with the testing criteria of the submitted test reports. If alternative designs, materials, proprietary products or construction methods different from that shown in the accepted plans are used, compliance with the relevant provisions under the Buildings Ordinance (BO) and the subsidiary legislations should be demonstrated when future plans are submitted for approval under the BO;
- (b) The MiC system is accepted based on the assumptions listed below. Overall stability, structural analysis, adequacy of structural member and/or structural connections, lateral deflection etc. should be checked when there are any deviations with future structural plans submitted for approval under the BO.
 - (i) Maximum building height from Ground Floor of 3.3m;
 - (ii) Maximum stack of modular units of one storey;
 - (iii) Design wind (unfactored) as shown on drawing no.: WHS/MIC/ST/0101;
 - (iv) Imposed loads, superimposed loads and other assumed loads as shown on drawing no.: WHS/MIC/ST/0101. Imposed loads for vehicular traffic are not considered;
 - (v) Lateral stability is provided by the modular units;
 - (vi) Fabrication and installation tolerances of modular units as shown on drawing no.: WHS/MIC/ST/0101; and
 - (vii) No stacking of modular units is allowed as shown on drawing no.: WHS/MIC/ST/0101.

Manufacturer and Prefabrication Factory

Details of the accepted manufacturer and prefabrication factory for fabrication of the modular units under In-principle Acceptance reference no. MiC 13/2020 for MiC system (Model No. MIC-RC-001) of Wing Hong Shun Enterprises Limited are as follows:

Manufacturer: Wing Hong Shun Enterprises Limited

Prefabrication Factory: Huizhou City Wing Hong Shun
Construction Material Co. Ltd.

Address of Prefabrication Factory: Bailianhu Village, Longxi Town,
Boluo, Huizhou, Guangdong, People's
Republic of China

Remarks:

- (a) *The above factory shall maintain a valid ISO 9001 or equivalent quality assurance certification at all times.*
- (b) *The following items in the Quality Assurance Scheme are for information only. Updated information should be submitted for future building projects with MiC.*
 - (i) *Frequency and extent of inspection by in-house staff and independent parties required in Appendix B of PNAP ADV-36; and*
 - (ii) *Frequency and extent of audit by in-house staff and independent parties required in Appendix B of PNAP ADV-36.*