

9 October 2024

Zhuhai Eastern Heavy Industry Co. Limited
Unit 902, 9th Floor, W668
Nos. 668/680 Castle Peak Road
Kowloon
(Attn: Mr. CHEUNG M. H. Jeff)

Dear Sir/Madam,

Letter of In-principle Acceptance
(Acceptance Reference No.: MiC 19/2024)

This letter is issued to **Zhuhai Eastern Heavy Industry Co. Limited** to confirm that the Modular Integrated Construction (MiC) system (Model No. **MIC-EASTERN-STEEL-01**) as submitted to the Buildings Department (BD) is acceptable in principle for use in private building projects in Hong Kong in respect of the performance aspects listed in Appendix I, subject to the following conditions:

- (i) The design and construction of any building project adopting the above MiC system shall comply with the provisions of the Buildings Ordinance (BO) and its subsidiary legislations;
- (ii) The conditions as set out in Appendix II and Appendix III shall be complied with;
- (iii) The modular units of the above MiC system shall be fabricated in the factories listed in Appendix IV with a valid ISO 9001 or equivalent quality assurance certification; and
- (iv) This in-principle acceptance (IPA) is valid for 5 years from the date of this letter.

2. General information of the MiC System (Model No. **MIC-EASTERN-STEEL-01**) submitted by **Zhuhai Eastern Heavy Industry Co. Limited** is available on BD's website.

/3. ...

3. Upon expiry of the IPA, application for its renewal should be prepared by an Authorized Person (AP) and Registered Structural Engineer (RSE). In case different AP and RSE are to be appointed, you are reminded to clarify any copyright issues.
4. This IPA shall not be construed as an exemption from obtaining prior approval and consent from the Building Authority under the BO before commencement of building works nor the granting of any exemption in gross floor area calculation.
5. This IPA does not give any warranties, explicit or implied, regarding their availability, efficacy, fitness for a particular purpose, title or non-infringement of copyright. The manufacturer/supplier/user must ensure that the above MiC system is safe for public use and complies with all relevant legislation and statutory requirements at all times.

Yours faithfully,



(CHAN Wai-tong, Victor)
Chief Officer/Technical Services
for Director of Buildings

c.c. CHEUNG Kong-yeung (Authorized Person)
c/o cheung kong - yeung architects ltd.
Room 1403A, 14/F, Block B
Sea View Estate, 2-8 Watson Road
North Point, Hong Kong

CHAN Ming-lung (Registered Structural Engineer)
c/o BeFrank Engineering Consultant Limited
Unit 501, 5/F, Kam On Building
No. 176A-F Queen's Road Central
Central, Kowloon

BD/MiC/230108(S)

**Applicable Performance Aspects
for In-principle Acceptance Reference No. MiC 19/2024**

The in-principle acceptance covers the following performance aspects of MiC system (Model No. **MIC-EASTERN-STEEL-01**) of **Zhuhai Eastern Heavy Industry Co. Limited** under the Buildings Ordinance (BO) and its subsidiary legislations:

- (a) Provisions of means of escape required under Part B of the Code of Practice for Fire Safety in Buildings 2011 (FS Code) and regulation 41(1) of Building (Planning) Regulations (B(P)R);
- (b) Provisions for fire resisting construction required under Parts C and E of the FS Code and section 35 of Building (Construction) Regulation (B(C)R);
- (c) Construction of external wall pursuant to sections 27 of B(C)R;
- (d) Height of storeys, provisions of natural lighting and ventilation required under regulations 24, 30 and 36 of B(P)R;
- (e) Sanitary provisions and associated drainage works within the modular units pursuant to Building (Standards of Sanitary Fitments, Plumbing, Drainage Works and Latrines) Regulations;
- (f) Structural performance for loads required under the Code of Practice on Wind Effects in Hong Kong 2019, the Code of Practice for Dead and Imposed Loads 2011 and Part 3 of B(C)R; and
- (g) Provisions for structural performance required under the Code of Practice for Structural Use of Steel 2011, the Code of Practice for Structural Use of Concrete 2013, the Code of Practice for Precast Concrete Construction 2016 and B(C)R.

2. For other performance aspects of the MiC system under the purview of the BO not listed above, compliance with the provisions of the BO and the subsidiary legislations shall be demonstrated when plans are submitted for approval under the BO.

**Acceptance Conditions (Building)
for In-principle Acceptance Reference No. MiC 19/2024**

The in-principle acceptance (IPA) of MiC system (Model No. **MIC-EASTERN-STEEL-01**) of **Zhuhai Eastern Heavy Industry Co. Limited** is subject to the following conditions:

- (a) This IPA is confined to adopting the MiC system for domestic use in a building not exceeding 4 storeys (maximum modular units of 4 storeys) as applied for;
- (b) The design and construction of MiC system should follow the plans accepted by the Buildings Department (Accepted Plans) and tally with the testing criteria of the submitted test reports. If alternative designs, materials or construction methods different from that shown in the Accepted Plans are used, compliance with the relevant provisions under the Buildings Ordinance (BO) and the subsidiary legislations should be demonstrated when plans are submitted for approval under the BO;
- (c) Authorized Person of the development project adopting the MiC system (AP) should ensure valid test and/or assessment reports complying the requirements under Part E of the Code of Practice for Fire Safety in Buildings 2011 would be available before the actual production in the prefabricated factory;
- (d) Applicant and AP should observe the requirements under Practice Note for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers APP-13 on submission of Schedule of Building Materials and Products and certifying the compliance with the relevant provisions of the BO upon completion of works;
- (e) Access points for inspection and future maintenance and repair of building services and construction elements should be provided in accordance with the Accepted Plans;
- (f) User manual with maintenance and building safety instructions for future fitting, decoration, alterations and additions of the modules as submitted with the application for IPA should be provided to the owners/occupants/users of the building adopting this MiC system; and

- (g) The IPA is subject to the grant of exemption/modification under section 42 of the BO for the following which would be favorably considered when relevant plans are submitted for approval under the BO:

BO/Building Regulations	Description
Regulation 35A of Building (Planning) Regulations	To accept non-provision of gas aperture in the bathroom in domestic premises

**Acceptance Conditions (Structural)
for In-principle Acceptance Reference No. MiC 19/2024**

The in-principle acceptance (IPA) of MiC system (Model No. **MIC-EASTERN-STEEL-01**) of **Zhuhai Eastern Heavy Industry Co. Limited** is subject to the following conditions:

- (a) The design and construction of MiC system should follow the plans accepted by the Buildings Department (Accepted Plans) and tally with the testing criteria of the submitted test reports. If alternative designs, materials, proprietary products or construction methods different from that shown in the Accepted Plans are used, compliance with the relevant provisions under the Buildings Ordinance (BO) and the subsidiary legislations should be demonstrated when future plans are submitted for approval under the BO;
- (b) The MiC system is accepted based on the assumptions listed below. Overall stability, structural analysis, adequacy of structural member and/or structural connections, lateral deflection etc. should be checked when there are any deviations with future structural plans submitted for approval under the BO.
 - (i) Maximum building height from Ground Floor of 12.88m;
 - (ii) Maximum modular units of 4 storeys;
 - (iii) Maximum design wind pressure is 1.99 kPa (unfactored);
 - (iv) Imposed loads, superimposed loads and assumed façade loads as shown on drawing no. GN/01 and LP/01;
 - (v) Lateral stability is provided by modular units only as shown on drawing no. GN-02;
 - (vi) Fabrication and installation tolerances of modular units as shown on drawing no. GN-01; and
 - (vii) No modular units are stacked more than one-storey above the completed floor as shown on drawing no. GN/02.
- (c) Structural details of in-situ R.C. structures (footing, E&M room, external staircase and ramp), metal roof at R/F, protective barrier, external wall/facade and A/C rack as shown on drawing nos. GN/01, L/01, L/02, X/01 and X/02 are not included in this acceptance.

Manufacturer and Prefabrication Factory

Details of the accepted manufacturer and prefabrication factory for fabrication of the modular units under In-principle Acceptance reference no.: MiC 19/2024 for MiC system (Model No. **MIC-EASTERN-STEEL-01**) of **Zhuhai Eastern Heavy Industry Co. Limited** are as follows:

Manufacturer: Zhuhai Eastern Heavy Industry Co. Limited

Prefabrication Factory:	Address of Prefabrication Factory	Production
Zhuhai Eastern Heavy Industry Co., Ltd.	West Side of Xincheng Avenue, Fushan Industrial Park, Qianwu Town, Doumen District, Zhuhai (Factory A)	Fabrication of modular units and concrete slab of modules

Remarks:

- (a) *The above factory shall maintain a valid ISO 9001 or equivalent quality assurance certification at all times.*
- (b) *The following items in the Quality Assurance Scheme are for information only. Updated information should be submitted for future building projects with MiC.*
 - (i) *Frequency and extent of inspection by in-house staff and independent parties required in Appendix B of Practice Note for Authorized Persons, Registered Structural Engineers and Registered Geotechnical Engineers (PNAP) ADV-36; and*
 - (ii) *Frequency and extent of audit by in-house staff and independent parties required in Appendix B of PNAP ADV-36.*